# 1 to 100



### Cisco Webex App

#### **Questions?**


Use Cisco Webex App to chat with the speaker after the session

#### How

- 1 Find this session in the Cisco Live Mobile App
- Click "Join the Discussion"
- 3 Install the Webex App or go directly to the Webex space
- 4 Enter messages/questions in the Webex space

Webex spaces will be moderated by the speaker until June 7, 2024.

https://ciscolive.ciscoevents.com/ciscolivebot/#BRKENS-3834






### Agenda

- Introduction
- Design and Deployment Best Practices
  - SDA & SDWAN Integration
  - 100,000ft view on Multi-Domain Design
- Deployment and Migration Lessons Learned from Large Scale Deployments
  - Having a solid Foundation
  - What is the migration process?
  - Lessons Learnt
- Conclusion



### Who are we?












Principal Architect


GES Architectures - CX

9+ Years @ Cisco

CCIE #28071 (R/S, SP)

CCDE #20210002






Specialized in: SD-Access, SD-WAN, MPLS, Multi-Domain Networks, Cloud, Automation

@DhruPrajapati



### Who are we?





### Jennifer Bowman

Sr. Delivery Architect

Cisco CX

9+ Years @ Cisco

CCIE #51241 (R/S, Security)

CCDE #2018::16

Specialized in: Full Enterprise IBN with Security and Automation

@ibnsrevenge


jdb1@cisco.com







Design and Deployment Best Practices




# Why Multi-Domain?

- Individual architectures introduce
  - Segmentation
  - Automation
  - Within a single enterprise domain



- Extend Segmentation
- Utilize orchestration
- Make the entire enterprise one IBN enclave



# What Is Involved In SDA & SDWAN Integration?

### Steps

- Catalyst Center and Manager integration
- SDWAN Manager owns each cEdge and assigns to CC
- Provision SDA specific changes through CC, SDWAN specific changes via Manager

#### Results

- SDA VNs and SDWAN Service VPNs tied together
- SDA SGT information propagated via SDWAN
- cEdge participates in both fabric domains
- Consistent application and security policy
- API based communication between CC and Manager

Host Name/IP Address 172.31.23.236

Username\*

admin

Password\*

.....

Port Number\*

8443

vBond Host Name/IP Address

vBondhosts

Organization Name

sdwan-overlay


Partner Id

5eebb9909962950017a3a725



BRKFNS-3834

### Really Really High-Level View





### 100,000 ft view


#### SDA

- Endpoints dynamically assigned SGTs and placed into VNs
- Macro and Micro-segmentation
- Unified wired and wireless networks

#### SDWAN

- Extends and bridges segmentation
- Applies CC per-VPN security and application policy.
- Enables end-to-end segmentation

What did we learn from Large Deployments?



# SD-Access and SDWAN Deployments





- Today available in partly manual "two-box" solution
- Two-box solution (non-integrated solution)
  - Clear demarcation between SDA and SDWAN architectures.
  - SDA BNs can be ISR4K, ASR1K or Cat9K switches, SDWAN edges can be ISR4K or ASR1K series routers
  - SD-Access and SDWAN designs can be implemented at a different pace



# SD-Access and SDWAN Deployments







- Majority of customers have employed two-box solution for modularity of deployment and flexibility in operations
- Mapping of VNs and VPNs is crucial
- Inter-site traffic flow greatly depends on SDWAN tunnel design and SDWAN underlay.
- For Multi-Regional (Global) networks, consistency across multiple CC clusters is key.
- Special consideration for inter-VN routing within the site




# SDA to SDWAN Integration (Two-Box)



Migrating The Beast!




cisco Live!




DNAC ISE integration

# Having a Solid Foundation




### 5 Pillars and a Bedrock





### Plan Design Implementation / AMO





Bringing stakeholders together



PMO: Build The City



Setting realistic schedules



Chase timelines and engineer requests








Bridging the gap and ensuring good customer sentiment

### Migration Team






Network Design Document

**BoM Preparation** 

**MoP** Preparation

Target Design




**Pre-Migration Window** 

Catalyst Center Configuration

Staging of Devices

**UAT** 



**Migration Window** 

Discover & Provision

Add to Fabric - L2/L3

**External Networks** 

Host Onboarding & Post Check




### Customer

#### Site Readiness Tasks

- ✓ Circuit ID and Handoff Type
- ✓ Site Technical POC
- ✓ Site Survey Information
- ✓ Decommission of Old Circuit

#### **Pre-Migration**

- ✓ Site Remediation Completed
- ✓ Adequate Power & Connectors
- ✓ Rack space & unmanaged devices



#### **Migration Window**

- ✓ User Acceptance Testing
- Circuit Provider Ticket if required
- ✓ Correct DNS on DHCP Scopes

#### **Post-Migration**

- ✓ Post Migration UAT
- Coordination with Cisco for wireless/wired Testing



### Partner

#### Staging

- Code Upgrade
- License & eWLC package
- Load Bootstrap
- Manager Reachability



#### Pre-MW

- Verify on-site inventory
- Rack, Stack, Power
- Cable all Devices



- Cable Moves as per MoP
- AP mounting
- Device Cleanup & Decommission





#### Readiness

- SFP : Copper & Fiber
- Cables: Console, Patch Cord
- Fibers: SMF, MMF
- Equipment: Label Marker



### Automation In SDA/SDWAN

### Why is it needed?



Large Site can have over 15000 endpoints

Validation & UAT can miss a lot of endpoints

### **How Automation Helps**



Underlay Config generator reduced MOP time



Reduced Migration Time with Fabric Config Generator




Site Snapshot & Overview of endpoints

#### **Automation Possibilities**


- Legacy Hardware Readiness & Assessment Tools
- Endpoint Discovery & Site Overview
- CC Site Hierarchy Push
- Fabric Fusion Config Generator
- Pre & Post Ping Sweep and Routing Delta



What is the Migration Process?



# Migration Pit Stops/Checkpoints



cisco live!

### Migration Approaches

### Single Step


- Move from current state to end state in 1 Maintenance Window
- Suited for Small Sites
- Process:
  - Move to SD-WAN
  - Replace and/or upgrade LAN switches to SD-Access
  - Migrate SD-Access Wireless

### Multiple Step


- Move from current to end state in multiple Maintenance Windows
- Suited for Medium to Large sites
- Process:
  - Day 1: SDWAN, Fusion and BN/CPs
  - Day 2+:Replace and/or upgrade targeted LAN closets to SD-Access
  - Migrate SD-Access Wireless



# Migration Approach - Single Step



Migration Approach - Multiple Step




### Multi Step Migration with L2BN Traffic Flow

 Any migrated subnet traffic between Legacy and Fabric will traverse through Layer 2 Border Node (L2BN)

 Any migrated subnet traffic between legacy and remote location will traverse through L2BN > BN/CP > Fusion > SDWAN

 Any migrated subnet traffic from legacy to nonmigrated subnet in legacy network will traverse through L2BN > BN/CP > Fusion > Legacy site

 Any non-migrated subnet traffic from legacy to remote location will traverse directly through Fusion > SDWAN






BRKFNS-3834

# Migration Approach - Final Step


- SDA Capable devices will be on boarded into the fabric
- Any temporary configurations will be cleaned
- Local C9800 WLC will be enabled for fabric mode and re-provisioned with fabric SSIDs
- All the APs will be provisioned to broadcast the fabric enabled SSIDs.






BRKFNS-3834

### SD-Access & SD-WAN Migration Steps






Lessons
Learned From
Large Scale
Migrations




### Technical Learnings





### Technical Learnings Continued...






# Operational Issues

On-Site	Ad-Hoc	Limitations	Others
Circuit Testing, Circuit Handoff & labelling	Project Milestones & RACI	Platform Limitation	Cross Team Dependency
Rack, Stack, Mount APs in Advance	Snowflakes per Request	High burnout rate	Hardware Upgrades
BoM Lead Time	Scoping & Resourcing	Accountability	Staging Facility
Spare SFPs, Cables	Site Variations & Consolidation changes	Endpoint Visibility	Compliance
Travel & Security Guideline	Unknown devices	Unmanaged Switches	Timely Approvals



BRKENS-3834

# Conclusion



# Key Takeaways





- Order of operations is key!
- Underlay of SDA and Trusted VN needs to be bridged to overlay of SDWAN
- DC first approach get those cEdge headends built first
- At branch, install SDWAN first, test it and then proceed with SDA
- Infrastructure and UAT testing is very critical
- TrustSec needs to be configured on SDWAN first and then SDA BN
- For sub-interfaces, TrustSec must be enabled on physical and all sub-interfaces



### Key Takeaways

- SD-Access and SD-WAN migrations can be done at rapid pace
- Consistency in design is key for at-scale migrations
- You are getting one chance to re-do the network take that opportunity!
- Remember those 5 pillars
- Automation is crucial for efficiency and accuracy
- BEAST is not as scary as it seems!
- Cisco CX is always there to work with you and accomplish success together.



### Complete Your Session Evaluations



Complete a minimum of 4 session surveys and the Overall Event Survey to be entered in a drawing to win 1 of 5 full conference passes to Cisco Live 2025.



**Earn 100 points** per survey completed and compete on the Cisco Live Challenge leaderboard.



Level up and earn exclusive prizes!



Complete your surveys in the Cisco Live mobile app.



# Continue your education

- Visit the Cisco Showcase for related demos
- Book your one-on-one Meet the Engineer meeting
- Attend the interactive education with DevNet, Capture the Flag, and Walk-in Labs
- Visit the On-Demand Library for more sessions at www.CiscoLive.com/on-demand



# Thank you

